

- 1- Details of Exhaust fan, electrification and lightening conductor for providing and fixing at Sri Kedarnath temple, District Rudraprayag.
- 2- The quantity of Unslaked lime may be read as 153.09quintals instead of 153.09cum.
3. The unslaked lime will be required time to time as per requirement of site.

1	Item No.8 Providing / fixing exhaust fans on the both side of the Antrala including the air flow ducts as well as suction pipe after removal of existing nonfunctional arrangement for exhaust etc. complete.				
	Exhaust fan (50 x 50cm) ISI mark Heavy Duty with G.I. sheet cover etc. complete.				2 Nos
	Air Flow duct				2 Nos
	Suction pipe complete				2 Nos
	Electric Switch Board power point with fitting MCB system Havells				2 set
2	Item No.9 Provision for providing / fixing appropriate wiring and electrical fixtures in the temple etc. complete.				
	Armed Cable Aluminium 3Phase (25mm ² x 4core)		-		200mtr
	Armed Cable Aluminium single Phase (10mm ² x 2 core)		-		150mtr
	Wire L&T 4mm ²		-		3 bundles
	Wire L&T 2.50mm ²		-		3 bundles
	MCB box (double door)		-		1No.
	MCB box		-		1No.
	MCB Havells 63Amp		-		13No.
	Mercury Light Bajaj complete set 240Watt		-		14No.
	Mercury Light Bajaj complete set 240Watt (Surface mounted LED light (Phillips/ Bajaj) 8"x 8", 10 Watt.)		-		12No
	Spiral pipe				150mtr
	Isolator 63Amp Havells				2No.

3	Item No.10 Provision for providing/fixing of lightening conductor of the Shikhara of the temple including testing commissioning etc. complete.			
	Copper Strip (40x5mm) 30mtr long @1.76kg/m		-	52.80kg
	Copper Plate 500x500x5mm		-	1No
	Copper Arrester complete		-	1No.
	Copper Clamp 25x5mm		-	60No.
	Copper Nails 3"		-	150No.
	Excavation of pit(0.60x0.60x1.50mtr)		-	1 No
	Charcoal		-	100kg
	Salt		-	100kg